Quality Roundtable at Renewable Energy India 2018



Boundaries conditions ensuring investor security in next-generation Indian PV projects

Initiative partner



Gold sponsors



LEONI → Solar-Log[™]



pv magazine group

September, 2018 – Quality Roundtable at REI

Case studies I & II

Panel I

Case study III

Panel II

Key takeways

pv magazine group

Case studies I & II



Asier Ukar Senior Consultant PI Berlin


pv magazine group





Case Studies on Quality Aspects of PV Power Plants in India

- Case studies and discussion -



PI Photovoltaik-Institut Berlin AG





1. Case study I: 1,505 kWp Rooftop

2. Case study II: 50MW Ground mounted





- The Owner, EPC and Operator are the same entity, hence, no EPC and O&M warranties are in place
- No binding **Provisional Acceptance Commissioning** (PAC) tests have been conducted
- No Owner's Engineer was appointed
- No Lender's Technical Advisor was appointed




Mounting structure

- The **longterm durability** of the foundation is not ensured
- Inaccurate module fixation was observed












 The electroluminescence and infrared analysis on a selected amount of PV modules confirmed the presence of PID




New Delhi, 19th September 2018



Operation and Maintenance



- The soiling losses are not measured onsite
- No O&M **reports** are issued
- The system availability and PR are not calculated
- The PV plant has no SCADA system







- 1. Case study I: 1,505 kWp Rooftop
- 2. Case study II: 50MW Ground mounted



- **Statics** do not consider maximum applicable wind loads
- Bad module fixation reduces the resistance against wind loads










Cable fixation and routing



- Cables in contact with sharp edges
- Cable ducts not sealed





Combiner boxes and inverters



Dust accumulation in combiner boxes and inverters





Grounding and equipotential bonding



Equipotential bonding conductor heavily damaged by salt corrosion





Weather station




- The module temperature is not measured
- The global horizontal irradiation (GHI) is not measured
- The metal arm fixing the pyranometer to the mounting structure is too long leading to an oscillation of the sensor when the wind blows







Inaccurate soldering was observed






Module handling



 Inaccurate module handling during construction and operation leads to mechanical damage of the cells





THANK YOU FOR YOUR ATTENTION

Dipl.-Ing. Asier Ukar Senior Consultant

PI Photovoltaik-Institut Berlin AG Wrangelstr. 100 10997 Berlin, Germany

phone: +49 (30) 8145264-402 cell-phone: +49 1777 44 7551 fax: +49 (30) 8145264-101 email: ukar@pi-berlin.com web: www.pi-berlin.com Alter PID

Voltage [V] 30 35

40

Panel I



Co-moderator

Asier Ukar Senior Consultant PI Berlin

pv magazine group





Rajaram Pai Business Leader South Asia





Rahul Sharma Senior Manager – Technical Applications





Jan Mastny Head of Global Sales

LEONI

pv magazine group



Case Study- Why Monitoring is required for a PV-Plant?

Quality Roundtable- REI (September 18, 2018)





Solare Datensysteme GmbH

CEO

Dr. Frank Schlichting, Brigitte Beck

Owner

BKW Group, www.bkw.ch

Headquarters

72351 Geislingen-Binsdorf – Germany

Product and market experience

> 10 years

BKW Energie AG




Founded 1909 in Bern, Switzerland


> 6000 employees worldwide

Delivering energy for ~1 billion people



New: Solar-Log India[™] - Cooperation with iPLON India








PV Monitoring with Solar-Log™

All relevant components of a PV system are monitored and controlled







iPLON's PV-DG Hybrid Controller

Technical Features

- Protection against reverse power current
- Suitable for Multiple DG sets
- Maintains the DG in the safe operating efficiency Diesel savings
- Fully automated system operation
- Remote maintenance and system management
- Active-Reactive Power control and Power Factor correction
- Inverter output control
- Compatible with all leading inverters



iPLON's Utility Solutions




Why Monitoring is the Brain of a PV System?

Case Studies (Failure Risk and Financial Consequences)

Maintenance programs with respect to Component failures

Component failure rate over time for component population





Intelligent Monitoring

			R		\$		
	O&M		Equipment Manufacturer		Asset Owners		Field Service Tech
✓	Track failures	✓	Measure failure rates	\checkmark	Understand revenue	✓	Pin-point failure
\checkmark	Track service	\checkmark	Better identify solution		loss	✓	Fix w/ minimum effort
	time			\checkmark	Improve budget	✓	Reduce down time
✓	Track truck rolls			\checkmark	Better est. equipment		
✓	Better define				replacement		
	KPI's & quality of						
	service						




Crucial Earnings Risks

Causes and Detection






Failure Areas (Relation to Tickets and Revenue Loss)





% Inverter Failure Areas







What is your definition of Qualified PV Monitoring & Management?

What are your expectations?


Which losses are significant enough to get involved if system components fail to work properly together?



34 www.solar-log.com

Analysis of existing plants


Proactive study - approach






Analysis of existing plants

Natural risks (annual weather-related yield deviation)



Forecasted target amount = 950 kWp per annum

Average yield per annum = 1010 kWp




(J) Solar-Log™

Analysis of existing plants

Natural risks (annual weather-related yield deviation)


Target-performance comparison over 5 years






Important Meteorological Measurements

Environmental Factors Influencing Solar Plant Performance (example with LUFFT)



Analysis of Existing Plants

Identification of typical errors



Which consequences or risks are connected to these error messages? => Simulation with error-free plants



Analysis of Existing Plants

Case Study 1: partial failure of one or several inverters

Assumption: 2 inverters (INV4+5) fail completely in August 2017 for 31 days and fixed after 5 days of detection



PV Plant	
PV Plant Size	52.38 kWp
Inverter power (INV 4+5)	20.16 kWp
Percentage INV 4+5 w/plant	38.5 %
No. of inverters	7
Performance of inverters	2x4;2x6,3x10 kW
Location	Germany, BW
Feed-In Tarif/ kWh	0,1069 € or 8.76 INR
Yield loss August 2017 (31 days)	2,904 kWh
Average yield loss within 5 days	468.54 kWh
Total Revenue loss after (31+5) days	29,543 INR/ 360 €



Analysis of Existing Plants

Case Study 2: Simulated partial failure of several strings

Assumption: 9 of total 12 strings failed, Completely undetected in May 2015 (31 days) and fixed after 5 days of detection



- 338kWp, 41 Inverters
- Chennai, India: Feed-in Tariff, INR 6.15/ kWh
- Annual Yield: 3,61,101 kWh
- 9 of 12 Strings Failed, Undetected for 31 Days
- Expected yield in May 2015 (31 days): 37,313.77
- 75 % yield loss in May 2015 (31 days): 27,985 kWh
- Average yield loss within 5 days after issue detection: 4,514 kWh
- Total Revenue loss after (31+5) days: 1,99,867 INR

Without professional monitoring the slight yield loss from module failure is hard to distinguish from natural fluctuations throughout the year, but even small yield loss equals a big financial loss!



Thank you very much

for your attention!

www.solar-log.com www.iplon.in










QUALITY IN PV

Illusion or reality

PV Magazine Quality Round Table September 18th, 2018 Jan Mastny

LEONI

Agenda





Products and solutions for your applications


Leading position in the automotive industry and in high-growth manufacturing markets





LEONI in figures


Close to our customers - worldwide



Stand 11/2017




LEONI Business Unit SOLAR & WINDPOWER




Quality? Where is the focus?



Hunting for the best cell efficiency



Glass properties have been in sight



Positioning of the module, ideal angles, improving impact of the right irradiance





Do you know, what is happening on the back side?



What Do We Hear?

2

 There are millions of modules in operation with very cheap components and nothing happened so far

 I ask the supplier to present the certificates, but I cannot do much more Are your connectors compatible to xyz?

> Your product is too expensive

LEON

 It is nice to get supplier's instruction manual, but we need to adjust to our process



5

The Weak Points

Manufacturing



- Recycled plastics/contaminated surface
- Absence of ESD care within production



- Color cables
- > Chemical cross-linking



- > Connector mismatch
- > Weak housing (cracking)

> Insufficient construction/design

CERTIFICATION DEVIATIONS




The Weak Points Installers



 Connector exposure to the outdoor conditions



> Bad handling of the cable



 Inproper attention to the junction box / components



Quality exists....



 Products from highly reputable manufacturers



- Long-term experience on the PV market
- > Trouble-free products



> Innovative mindset



The Solution

1

2

3

4

5

 Reputation and long-term stability of the supplier

- Observe and witness the suplier's quality related processes and quality mindset
- Observe the investments to the research (investment to the future)
- Follow the supplier's assembling/use instructions
 - > See, whether the the specification and certification is alligned

- Care about the materials/components being used
- Use identical connectors/components in the whole array
- Compare aples with aples only
- Educate the installers

6

7

8

9



Education Goes Further

Be part of it!






Webinar - how to recognize the key indicators of quality

Focused on cables, connectors and junction boxes

The purpose is to show some examples of failures consequences caused by lack of knowledge and/or motivated with an (unreasonably) attractive pricing

Moderated by: Faruk Yeginsoy Jan Mastny

Date & Time: November 15th, 8:00AM CET









THE QUALITY IS NOT EVERYTHING. BUT EVERYTHING WITHOUT QUALITY IS NOTHING! (CAPEX vs. OPEX)



STUDY THE PRODUCT, STUDY THE SUPPLIER



IT IS BETTER TO LEARN FROM THE MISTAKES OF THE OTHERS, RATHER THAN FROM YOUR OWN



THANK YOU FOR YOUR ATTENTION



LEONI – Business Unit Solar & WIndpower > Head of Global Sales Jan Mastny > Address Herrenmattstr. 20 4658 Däniken **Switzerland** > Phone +41 797-904-828 > E-mail jan.mastny@leoni.com > Homepage

www.leoni-solar-windpower.com






GW Scale Policy + Financing

Policy and financing change is accelerating




Institute for Energy Economics and Financial Analysis IEEFA.org

Vibhuti Garg <u>vgarg@ieefa.org</u> 18 September 2018



Due to escalating pollution pressures and steep price declines in renewable energy tariffs & rising coal costs, solar is picking up in a big way in India





- Utility Scale Solar Parks
- Rooftop Solar
- Wind- Solar Hybrid

- Floating Solar
- Solar PV with Storage

3. Government Policies incentivising Solar PV in India

62



- 1. Viability Gap Funding: Under the reverse bidding process, bidders who need least viability gap funding at the reference tariff selected.
- 2. Accelerated depreciation: For profit-making enterprises installing rooftop solar systems, 40% of the total investment could be claimed as depreciation in the first year (decreasing taxes).
- **3. Clean Energy Cess:** A National Clean Energy Fund (NCEF) created from the cess aims to fund clean energy projects and provide up to 40% of the total costs of RE projects through the Indian Renewable Energy Development Agency (IREDA).
- 4. Capital subsidies were applicable to rooftop solar-power plants up to a maximum of 500 kW. The 30% subsidy was reduced to 15%.
- 5. Renewable Energy Certificates (RECs): Tradeable certificates providing financial incentives for every unit of green power generated.
- 6. Net Metering: Depend on whether a net meter is installed and the utility's incentive policy.
- 7. Assured Power Purchase Agreement (PPA): The power-distribution and -purchase firms owned by state and central governments guarantee the purchase of solar power when produced.
- 8. Interstate transmission system (ISTS) charges and losses are not levied during the period of PPA for the projects commissioned before 31 March 2022.
- **9.** Safe guard duty : To protect the local solar panel manufacturers, 25% safe guard duty is imposed for two years period from August 2018 on the imports from China & Malaysia.

A key landmark in the evolution of India's solar sector was the launch of the Jawaharlal Nehru National Solar Mission (JNNSM) in 2010. This set a target of 20 GW by 2022, which was easily achieved by 2013



4. Subsidies & Impact of GST

S.No.	Subsidy	Mechanism	Beneficiary	FY 14	FY 15	FY 16
1	Viability Gap Funding (VGF) Scheme- 750 MW, 2000 MW, 5000			468.8	468.8	968.8
2	Scheme for development of Solar Parks and Ultra Mega Solar P			not in place	172.5	365.7
3	Grid Connected SPV Rooftop and small solar power programme				3.7	4.0
4	Scheme for setting up of over 300 MW of solar power projects by			not in place	150.0	150.0
5	Scheme for setting up of 1000 MW of Grid-Connected Solar PV			not in place	not in place	128.8
6	Financing and non-financing schemes: IREDA and other organis	Direct and indired	Production	39.3	77.1	122.4
7	Canal Bank/ Canal Top Scheme	Direct and indired	Production	not in place	69.0	76.0
8	Accelerated Depreciation	Government reve		909.0	2686.0	3885.0
9	Tax breaks on Excise and Custom Duty: Solar & Wind	Government reve		642.0	1682.0	2365.0
10	Tax breaks on GST: Solar and Wind	Government reve	Production	not in place	not in place	not in place
	Total			2060.6	5309.1	8065.7





Tax breaks and Viability Gap funding are the largest form of government support to Solar sector. Subsidies have increased in FY17 & FY18 but will diminish in FY19 with the safeguard duty.

As per MNRE estimates, GST will result in a 6% rise in total project costs

Part of production chain	% of Total levelized cost of electricity (LCOE) Tariff	Capital cost heads	% of Sub- Total (Pre- GST)	Pre-GST taxrate	GST1
	80.5 - 88.5%	PV Modules	51%	0%	5%
		Land Cost	6%	0%	0%
		Civil and General Works	9.5%	4%	5%
Upstream		Mounting Structures	6.5%	12.5%	5%
Ups		Power Conditioning Unit	6.5%	12.5%	5%
		Evacuation Cost	15%	12.5%	5%
		Soft Cost	5.5%	14.5%	18%
Downstream	11.5 - 19.5%	Operations & maintenance	100%	14.5%	18%
		Total	100%		










Source: Bloomberg NEF

6. Renewables have overtaken Thermal Power



India Renewable and Thermal Power Capacity Additions (MW)


Source: Central Electricity Authority of India (CEA), MNRE India, IEEFA estimates



7. New Age Financing Option



- India needs US\$140 Billion investment in Renewable Energy by 2020 to meet its requirements.
- The infrastructure financing gap due to reduction of capital available from traditional sources underscores the need for encouraging emerging and alternate sources of funding






8. Challenges

Biggest concern in the sector


According to the survey, the biggest concern for the sector is grid integration of growing renewable capacity followed by poor financial condition of DISCOMs, notwithstanding the progress made on UDAY reform package.



Sor Paul Arry Ner Di /AC Inverter

Fear of poor quality equipment being dumped in India

52% of the respondents feel that this a very high risk. 39% of the respondents have indicated that this is a real but manageable risk and only 3 respondents (10%) feel that there is no such risk. This response should be an alarm call for the government and policy makers.



Grid availability and integration, tax reform access to finance & quality control is key for sustainable development



9. Way Forward

- Innovative financial instruments will need to be further explored to reduce cost of debt in India and scale up infrastructure investment.
- Falling tariffs are making earlier projects unviable (beware reneging on existing contracts). Also, there is risk of delivery or servicing debt obligation at very low rates. Developers to account for such risk appropriately in their bids.
- Policy certainty in long term for building confidence of developers and investors. Price cap, safeguard duties to be avoided till the domestic manufacturing capacity is developed.
 Energyworld
- Solar resource forecasting and grid integration planning.

500 MW Gujarat solar tender oversubscribed 4 times

Gujarat Urja Vikas Nigam Limited (GUVNL)'s re-tender of the annulled 500 MW gridconnected solar PV tender has been oversubscribed by almost four times. Technical bids aggregating 1,925 MW have been submitted against the tendered capacity of 500 MW

SEPTEMBER 10, 2018 PREETI VERMA LAL

INDIA DURING UTLITESCALE PV GUIART INDIA

Image: Filpro - File:India grey:svg, CC BY-SA 4.0, https://commons.wikimedia.org/windex.php? curid=50749771

Share 🚺 💙 🗇 🥝

A total of 13 participants have submitted bids, including big players like Azure (\$00 MW), Aditya Birla (250 MW), Adani (200 MW), Mahindra (200 MW), and Feyman (100 MW).

In February of this year, GUVNL floated the 500 MW tender with a 'greenshoe' option, meaning additional capacity could be awarded based on the L1 tariff of this tender. The technical bids received on the back of this were oversubscribed by three times.







 Renewable >
 Solar power
 Solar Power Bids
 Solar tariffs
 Solar power news
 solar power india

 India solar power
 economy policy

 <td

India solar power target under cloud as agencies spike bids for 9,000 MW

The cancelled tenders represent half of the 18,000 MW bid out by these agencies till August. The cancellations coincide with the pace of solar capacity addition dropping 52% to 1,599 MW in the April-June period from 3,344 MW in the January-March period of 2018.



68

Case study III



Jitendra Moranka VP Global Design Applications NEXTracker

A Flex Company

pv magazine group



Case Study 30MW CLEANMAX Eluvanampatti Solar Farm, TN, India Field Trial

TRUECAPTURE - BOOSTING ENERGY YIELD WITH SMART CONTROL TECHNOLOGY

Jitendra Morankar VP Global Design Applications

18 Sept 2018 REI Expo, New Delhi, India



INDIA SITES - CHALLENGES

No Grading – Undulating Sites:

- Land acquisition delays
- Hydrology & environmental impact
- Lack of heavy machinery
- Lack of skilled labor
- High cost of grading

Consequences:

- Row to Row Shading
- Construction variance





NEXTracker A Flex Company

REAL WORLD CONDITIONS CAN LIMIT PRODUCTION

Row-to-Row Height Variances

The World is Not Flat

- Terrain undulations
- As-Built construction variances
- Nearby geographic features

Diffuse Irradiance

- Overcast/ clouds
- Fog
- Heavy haze or pollution





NEXTracker A Flex Company

TRUCAPTURE[™] SMART CONTROL SYSTEM

A Flex Company

TRUCAPTURE[™] SMART CONTROL SYSTEM

Standard Tracker



With Row to Row TrueCapture





NX HORIZON SMART SOLAR TRACKER

Zigbee wireless mesh network connects controller on each tracker row to the NCU

NX trackers combine advanced mechanical design with digital communications & control to maximize project IRR

DC Motor drives tracker row

4

Self Powered Controller (SPC) precisely measures array angle and controls tracker position. Integrated Li-Ion backup battery provides power reserve and overnight control

Dedicated smart PV panel powers self-powered controller and motor

30MW CLEANMAX Eluvanampatti Solar Farm, TN, India






TRUECAPTURE[™] FIELD TRIAL – 2 Months (July 2nd to August 28th)

5MW Blocks selected for trial

Row to Row and Diffuse TRUECAPTURE implemented






NEXTracker: A Flex Company

roprietary and Confidential ©2017

REPRESENTATIVE ROW TO ROW COMPARISON


CleanMax Inverter Block 2 1.83MW AC Inverter, TMEIC | DC:AC = 1.36 | 30 MW total capacity




REPRESENTATIVE ROW TO ROW COMPARISON

TrueCapture generates more energy

CleanMax Inverter Block 2 1.83MW AC Inverter, TMEIC | DC:AC = 1.36 | 30 MW total capacity




TRUECAPTURE ENERGY YIELD BENEFIT



Simulated example – one typical day on 1 MW site


CleanMax – TrueCapture Combined



NEXTracker: A Flex Company Proprietary

FIELD TRIAL RESULTS FOR 2 MONTH PERIOD

TrueCapture generated 2.96% more energy production overall (row-to-row & Diffuse)



India Site Challenges – Open Discussion



Q & A

Extracker A Flex Company



Proprietary and Confidential ©2018

Panel II



Co-moderator

Jitendra Moranka VP Global Design Applications



pv magazine group

Panel II



Shailesh Bijegaonkar Sales Manager India





Robin Li Global Technical Service and Product Management Director Jinko Solar




George Touloupas Director of Technology and Quality




pv magazine group

STÄUBLI ELECTRICAL CONNECTORS – YOUR BANKABLE PARTNER Stäubli Group – three activities, four divisions





Failures and their financial impact




PROJECT BANKABILITY - CONTACT RESISTANCE

Why connectors can have this big impact

Constant low contact resistance = **Long-term reliability and efficiency**


Stäubli




PROJECT BANKABILITY – DETAILS MATTER



Contact resistance – main risk sources



PROJECT BANKABILITY – QUALITY SAFES Impact on LCOE (Levelized Cost of Electricity)



STÄUBLI

Photovoltaic & Advanced Materials

Sept. 2018

PV Field Study



DOI




Cracking of Glass-Glass modules

~10% glass breakage of 1MW bifacial modules, after 2 years installation in western China




Lower module power generation of Glass-Glass vs. Glass-Backsheet



DuPont Photovoltaic & Advanced Materials 94

Significant corrosion and power loss of Glass-Glass modules



15 years in South China, tropical climate

PVDF film-based backsheet cracked in field



5 years

4200

North America

Summary


- 36% modules have backsheet cracking and delamination
- PVDF film on backsheet outer layer cracking in Machine Direction

- Initial year of operation
 2012
- Service Time
- Location
- Date of inspection
 Aug, 31, 2017
- # of modules
- System size 993.6 kW

- Mounting configuration
- Fixed tilt or tracking
 - Backsheet:
- Module Maker
- Technology


Ground open rack Fixed Tilt PVDF Same for both types mono-Si

PVDF film-based backsheet cracked in field



Severe yellowing of inner layer of PET (10-15%) and chalking of Polyamide based backsheets (10 – 15%)

Plant Type	Ground Mounted, On- grid
Initial Date of Operation	Feb, 2012
Location	Fatehpur Village, Gujarat
Plant Size	5 MW
Pmax (Wp)	240
Total No. of Modules	20800
Tracking	Fixed Tilt 40°
Ground Surface	Dry Grass + Sand
Backsheet	PET, PVDF, FEVE, Polyamide



Severe yellowing of PET Based Backsheets

Chalking of Polyamide based backsheet

PFAVE backsheet cracking: observed in ~80% of the installed modules

Item	Details
Plant Type	Ground Mounted
Date of Inspection	23 June 2017
Initial Year of Operation	2008
Location	Jamuria, Kolkata
Tracking	Fixed Tilt
Climate	Warm & Humid
Pmax (Wp)	235 Wp (60-cell) (multi)
Initial Plant Capacity	0.9 MW
Current Plant Capacity	0.88 MW
Total No. of Modules	~4000
No. of operational modules	~3900
No. of modules removed	~100
Backsheet	PFAVE

Thank You





©2018 DowDuPont, The Dow Chemical Company, DuPont. All rights reserved. ®™ Trademark of DowDuPont, The Dow Chemical Company, E.I. du Pont de Nemours and Company, or their affiliates.

Key takeaways



Asier Ukar Senior Consultant PI Berlin

pv magazine group





Pilot Study on Quality Aspects of PV Power Plants in India

- Take away messages-



New Delhi, 19th September 2018

PI Photovoltaik-Institut Berlin AG



Take-away messages (1/3)



¹ The tender requirements shall include strict quality criteria applicable to the whole value chain. Special focus shall be put on the long term durability of PV modules and DC cables, electromechanical installation and commissioning.

² The performance warranties along with the applicable pass fail criteria should be clearly expressed in the EPC and O&M contracts in order to reduce the risks of the solar power developers (SPD).

In projects financed, constructed and operated by the same company, EPC and O&M contracts may not exist. Thus,

3 external third party inspection should be mandatory since self-imposed quality control measures are usually not applied by the SPDs.



LTAs and OEs play an important role during the development process helping banks and SPD to detect failures at early stages.

The design of a PV plant shall be orientated towards a minimization of the LCOE. Decisions orientated towards a low initial investment provide a benefit in the short term but do not necessary lead to higher profitability.

5



Take-away messages (2/3)



- 6 The awareness of the construction companies in regards to the consequences derived from the installation failures should be increased in order to prevent costs, safety issues and performance drops.
 - The EPC shall be liable for the installation failures. The technical requirements for allowing a proper identification of the same shall be annexed to the EPC contracts.
- 8 The tender requirements shall ensure that all PV plants are commissioned according to the industrial best practices of the PV industry in regards to performance and safety aspects, both on system and component level.



- Clear installation guidelines and a comprehensive BOM of the weather station shall be part of the tender requirements in order to ensure a proper logging of all relevant environmental variables responsible for an accurate Performance Ratio assessment.
- 10 The yield simulations issued prior to financial close shall be aligned with the industrial best practices in order to ensure the bankability of the project.

7

9



Take-away messages (3/3)



- 11 The module suppliers shall prove evidence of quality not only in regards to the basic IEC certification but also considering Indian specific environmental stress factors.
- 12 Factory audits and production supervision of PV modules shall be part of the tender requirements avoiding low quality modules reaching the PV facilities.
- 13 Before starting the operational phase, the impact of the cleaning methodology on the module warranty shall be assessed.



¹⁴ A strong O&M reporting including the monitoring of the system availability contributes to an accurate tracking of a PV plant behavior.

THANK YOU FOR YOUR ATTENTION

Dipl.-Ing. Asier Ukar Senior Consultant

PI Photovoltaik-Institut Berlin AG Wrangelstr. 100 10997 Berlin, Germany

phone: +49 (30) 8145264-402 cell-phone: +49 1777 44 7551 fax: +49 (30) 8145264-101 email: ukar@pi-berlin.com web: www.pi-berlin.com Alter PID

Voltage [V] 30 35

40

See you at our next Quality Roundtable in...

Anaheim



Melbourne







pv magazine group

September 2018 – Quality Roundtable at REI